



NOTES

1. All dimensions are in millimeters unless stated otherwise
2. foundations and columns will be class 30 concrete cured at least 14 days morning and afternoon
3. Ground beam and coping beam will be class 20 cured at least 14 days morning and afternoon
4. Walls will be constructed with well dressed(Dhagax cad)
5. Plastering of walls should be smooth and steel float should be used
5. The perimeter wall shall have 400mmx 450 concrete column in every 6m

Client World Vision Somalia,Garowe

PROJECT Construction of Perimeter wall